S.No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS / Number	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Character s)
1		Construction of temporary toilets on hire basis. The compartments shall be made of fibre/ sunglass and Roofing with fiber of suitable size as per standards W.C pan with foot rests. Water tap, lighting and ventilating provision shall be made compartments shall have septic tank/ Bio digestion facility. Water supply arrangements with sufficient storage capacity shall be made. Attendants shall be providing round the clock minting the toilets. cleaning the toilets with disinfection solutions frequently shall be done at regular interval septic tank / Bio digest shall be cleaned as regular intervals shall be done and convey the night soil to suitable dumping place as directed by the departmental authorities including providing Napa slabs on the path ways as directed by the executive authority. The temporary toilets shall be maintained upto completion of Dussarah festival and it may be increased/decreased and can be Extended for the next few days as per the orders of the Departmental authorities with the same rental cost per day. After completion of the program the entire structure shall be removed from the site should be cleaned as it is. This rate includes cost and conveyance of all materials, labour charges, etc., complete and as directed by the Engineer incharge.	have septic tank/ Bio digestion facility. Water	on hire basis. The compartments shall be made of fibre/ sunglass and Roofing with fiber	As directed by Engineer in charge		
а	16.00	Durga Ghat	Durga Ghat	Durga Ghat	As directed by Engineer in charge	2210/Day X 12 Days	No's
b	29.00	Dhobi Ghat or Krishnaveni Ghat	Dhobi Ghat or Krishnaveni Ghat	Dhobi Ghat or Krishnaveni Ghat	As directed by Engineer in charge	2210/Day X 12 Days	No's

Amount (INR) (Upto 2 Decimals)

4,24,320.00

7,69,080.00

11,93,400.00

29835