

**SRI DURGA MALLESWARA SWAMY VARLA DEVASTHANAM, INDRAKEELADRI, VIJAYAWA**

**Estimate**

**Name of work: PROVIDING TEMPORARY SHAMIYANAS & WATER PROOF SHEDS AT DOWN H DASARA - 2018**

S.No	Description of work	No	Measurements			Contents	Rate	Per
			L	B	D			
1	Hire charges for erection and removal of flat roof 100% water proof sheds with MS trusses, I sections channels etc., with necessary frame work with intermediate posts. The roof covering with GI Sheets and duly providing white/multi colour ceiling cloth for decorating the shed with necessary frame work with .decorative frills (Jallars) around and border and wherever necessary etc., complete and duly covering the shed with water proof curtains on one sides of the shed as directed during execution from competent authority watch and ward against theft and fire accidents, to and fro transportation charges and all labour, incidental charges etc., complete The ceiling cloth should be white/multi in colour and should be in a good condition throughout the festival and should be removed after the same is over The contractor should allow the electric and flowers decoration over the cloth done departmentally without any claim including maintenance during the said period. The rate is for festival period as decided by the							
	Keshakandasala	1x1	48.77	24.35		1,187.55		
	Mahamandapam(South side)	1x1	12.34	11.89		146.72		
	Mahamandapam(East side)	1x1	49.38	11.58		571.82		
	Mahamandapam(East side)	1x1	30.48	6.10		185.93		
	Kalaaradhana	1x1	31.09	17.68		549.67		
	Kanaka Durga Nagar Prasadam Counters	1x1	18.59	17.68		328.67		
	Kanaka Durga Nagar Prasadam Counters	1x1	25.00	24.08		602.00		
						<b>3,572.36</b>	<b>Sqm</b>	<b>280.00</b>
								1 sqm
2	Hire charges for erection and removal of Flat roof or sloped roof 100% water proofpendals covering with plastic tarpaulin with casuarina/MS pipes frame work, White/colour ceiling cloth with frills for decorating the shed and Plain border around complete.The rate includes watch and ward against theft and fire accidents, to and fro transportation charges and all labour chages etc, complete and should be in a good condition throughout the festival and should be removed after the same is over.if the cloth is spoiled due to rain the contractor should allow the electric and flowers decoration over the cloth done departmentally without any claim including maintainance during the said period. The rate is for festival period as decided by the devasthanam for festival days							
	<b><u>Down Hill</u></b>							
	vinayaka temple to Boddu Bomma	1x1	30.00	$\frac{4.30+3.90}{2}$		123.00		
		1x1	26.75	$\frac{3.9+3.66}{2}$		101.11		
	De opening(-)	1x1	2.13	$\frac{3.9+3.66}{2}$		-8.05		
		1x1	31.60	$\frac{3.66+3.76}{2}$		117.24		
	De opening(-)	1x1	2.13	3.76		-8.00		
		1x1	103.35	$\frac{3.81+3.76}{2}$		391.18		
		1x1	100.10	$\frac{3.81+3.76}{2}$		378.88		
		1x1	68.43	$\frac{3.81+3.76}{2}$		259.00		
	Up to Boddu Bomma	1x1	20.42	$\frac{3.86+3.28}{2}$		72.90		
	Boddu Bomma to ashok pillar	1x1	28.50	$\frac{3.28+4.04}{2}$		104.31		

S.No	Description of work	No	Measurements			Contents	Rate	Per
			L	B	D			
		1x1	34.14	$\frac{4.04+4.88}{2}$		152.26		
		1x1	32.00	$\frac{4.88+5.13}{2}$		160.16		
		1x1	31.55	$\frac{5.13+4.78}{2}$		156.33		
		1x1	33.68	$\frac{4.78+4.22}{2}$		151.56		
		1x1	29.11	$\frac{4.22+4.42}{2}$		125.76		
		1x1	9.52	$\frac{4.42+6.10}{2}$		50.08		
		1x1	6.47	$\frac{6.10+4.17}{2}$		33.22		
	Foot over Bridge	1x1	20.73	2.95		61.15		
	Ashok pillar to Toll gate	1x1	29.03	3.35		97.25		
		1x1	61.57	$\frac{3.35+3.66}{2}$		215.80		
		1x1	32.23	$\frac{3.66+3.66}{2}$		117.96		
		1x1	36.58	$\frac{3.66+3.45}{2}$		130.04		
		1x1	46.02	3.45		158.77		
	Police out post	1x1	7.01	5.49		38.48		
	Boddu Bomma to Vinayaka Temple Bazar Road Side	1x1	31.55	$\frac{2.81+2.49}{2}$		83.61		
		1x1	32.54	$\frac{2.49+3.40}{2}$		95.83		
		1x1	63.96	$\frac{3.40+3.28}{2}$		213.63		
		1x1	207.72	$\frac{3.28+3.56}{2}$		710.40		
	Tollgate to Kummari Palem	1x1	28.04	2.74		76.83		
		1x1	45.72	$\frac{2.74+3.05}{2}$		132.36		
		1x1	345.95	3.05		1,055.15		
	Kanaka Durga Nagar annadanam Q lines	1x1	29.26	2.90		84.85		
		1x1	13.41	1.07		14.35		
	Ramp	1x1	32.00	0.91		29.12		
	Annadanam Opp	1x1	3.20	1.83		5.86		
	Kanaka Durga Nagar sarees sales counter and Devasthanam Stall and medical depts	1x1	16.46	5.49		90.37		
	Medical and all other depts	1X1	10.97	5.49		60.23		
	dress changing room1	1X1	10.97	5.49		60.23		
	for department staff	1X1	5.49	3.66		20.09		
	motor room	1X1	5.49	5.49		30.14		
	Keshakandanasala Ticket Counters	1X1	30	15.00		450.00		
	<b>Padmavathi Ghat</b>							
	Medical and all other depts	1X1	8.80	3.90		34.32		
	dress changing room1	1X1	7.10	3.10		22.01		
	<b>Seetamma Vari padalu Ghat</b>							
	Medical and all other depts	1X1	12.2	4.70		57.34		
	dress changing room1	1X1	8.1	3.00		24.30		

S.No	Description of work	No	Measurements			Contents	Rate	Per
			L	B	D			
	dress changing room2	1X1	7.8	2.90		22.62		
	dress changing room3	1X1	8.2	3.00		24.60		
	<b>Durga Ghat</b>							
	Medical and all other depts	1X1	10	3.25		32.50		
	dress changing room1	1X1	8.4	3.80		31.92		
	Medical and all other depts	1X1	5.49	2.74		15.04		
	Majeti Kalyana Mandapam	1X1	21	7.00		147.00		
	add 5% area variations					340.25		
						<b>7,145.33</b>	<b>Sqm</b>	<b>160.00</b>
								<b>1 Sqm</b>
3	Hire charges for supplying, laying and removal cultural activities Stage ( Iron Jacky type) The rate includes watch and ward against theft and fire accidents to and fro transportation charges and all labour, incidental charges etc., complete. The Stage should be in a good condition through out the festival and should be removed after the same is over.The rate is for festival period as decided by the devasthanam.							
	Kalaradhna Stage.	1x1	40' 0"	20' 0"		800.00	Sft	<b>65.00</b>
								<b>1 Sft</b>
4	Dismantling of rigid pavement / flexible pavement/hard rock of depth 300 to 450 mm by making holes using prematic compressor for drilling of 4 Nos of 25 mm dia to a depth of 300 to 450 mm including removal of CC/BT surface by dismantling drilled surface using hammers including all labour charges etc., complete The rate is for festival period as decided by the devasthanam for festival Days.							
	Vinayaka Temple to Tollgate Bazar Road side	1X148				148.00		
	Divider side	1X 343				343.00		
	Cannel Road side	1X 342				342.00		
	add 10% area variations					83.30		
						<b>916.30</b>	<b>Nos</b>	<b>70.00</b>
								each
5	Hire charges for supplying, laying and removing of shamiyanas with Bamboo posts or casuriana posts with necessary frame-work , tables, chairs and other materials etc., The rate includes watch and ward against theft and fire accidents, to and fro transportation charges and all labour, incidental charges etc., complete. The shamiyanas should be in a good condition throughout the festival and should be removed after the same is over.The contractor should be supplying the materials whenever necessary during the festival period. The rate for each item is for festival period as decided by the devasthanam including maintenance during the said period including laying,removing,loading, unloading, transport charges.							
	<b>Providing side walls of size 18'-0"x6'-0"</b>							
	Mahamandapam kalaradhana Green room.	1X3				3.00		
	Kanaka Durga Nagar Prasadam stock point	1X2				2.00		
	Sarees sales counter	1X4				4.00		
	<b>Padmavathi Ghat</b>							
	Medical and all other depts	1X4				4.00		
	dress changing rooms	1X8				8.00		
	<b>Seetamma Vari padalu Ghat</b>							

S.No	Description of work	No	Measurements			Contents	Rate	Per
			L	B	D			
	Medical and all other depts	1X6				6.00		
	dress changing room1	1X8				8.00		
	dress changing room2	1X8				8.00		
	dress changing room3	1X8						
	clock room	1X2				2.00		
	<b>Durga Ghat</b>							
	Medical and all other depts	1X3				3.00		
	dress changing rooms	1X5				5.00		
	<b>Bhavani Ghat</b>							
	Medical and all other depts	1X6				6.00		
	<b>Punnami Ghat</b>							
	Medical and all other depts	1X3				3.00		
	<b>TTD Site</b>							
	Medical and all other depts	1X2				2.00		
						<b>64.00</b>	<b>Nos</b>	<b>60.00</b>
								each
	<b>Providing side walls of size 18'-0"x10' 0"</b>							
	South Side	1X6				6.00		
	<b>K K sala inside</b>							
	Medical and all other depts	1X1				1.00		
	power room	1X3				3.00		
	staff room	1X11				11.00		
	for shed on north side	1X7				7.00		
	ladies dress changing room	1X23				23.00		
	motor room	1X4				4.00		
						<b>55.00</b>	<b>Nos</b>	<b>80.00</b>
	<b>Providing silk curtains 18'-0"x10' 0"</b>							Each
	Kanaka Durga Nagar point	1X6				6.00	<b>Nos</b>	<b>110.00</b>
								each
	<b>Providing Fibre chairs</b>							
	Mahamandapam Kalaradhana Insaide	1X280				280.00		
	For tepposthavam	1X230				230.00		
	Kanaka Durga Nagar medical	1X30				30.00		
	Sarees sales counter	1X10				10.00		
	Photo stall Sound system	1X20				20.00		
	Laddu Prasadam counter	1X40				40.00		
	Toll gate	1X20				20.00		
	Forest Dept	1X10				10.00		
	<b>Padmavathi Ghat</b>							
	Medical and all other depts	1X23				23.00		
	<b>Seetamma Vari padalu Ghat</b>							
	near under passege for water packets point and clock room	1X6				6.00		
	for handicapped and senior citizens	1x5				5.00		
	Medical and all other depts	1x18				18.00		

S.No	Description of work	No	Measurements			Contents	Rate	Per
			L	B	D			
	<b>Durga Ghat</b>							
	Medical and all other depts	1X24				24.00		
	<b>Bhavani Ghat</b>							
	Medical and all other depts	1x20				20.00		
	<b>Punnami Ghat</b>							
	Medical and all other depts	1x17				17.00		
	<b>TTD Site</b>							
	Medical and all other depts	1X10				10.00		
	<b>K K sala inside</b>							
	KK sala inside	1x800				800.00		
	<b>vinayaka swamy temple</b>							
	Medical and all other depts	1x35				35.00		
	Kummaripalem Medical Camp	1X4				4.00		
	sithara centre for police out post	1X4				4.00		
	at C.V.R. fly over medical camp	1X4				4.00		
	chittinagar centre for police out post	1X4				4.00		
						<b>1,614.00</b>	<b>Nos</b>	
							<b>49.00</b>	
							Each	
	<b>Providing iron tables</b>							
	Mahamandapam Kalaradhana green room	1X11				11.00		
	Keshakandana sala Medical and all other depts	1X10				10.00		
	sarees sales counter	1X30				30.00		
	Sound system forest dept	1X25				25.00		
	Tollgate police, Medical	1X8				8.00		
	Vinayaka Temple Medical	1X4				4.00		
	Keshakandana sala Medical and all other depts	1X6				6.00		
	inside kk sala	1X5				5.00		
	Tollgate police, Medical	1X8				8.00		
	Vinayaka Temple Medical	1X7				7.00		
	<b>Padmavathi Ghat</b>							
	Medical and all other depts	1X7				7.00		
	<b>Seetamma Vari padalu Ghat</b>							
	Medical and all other depts	1X6				6.00		
	near under passege for water packets point and clock room	1X10				10.00		
	<b>Durga Ghat</b>							
	Medical and all other depts	1X6				6.00		
	<b>Bhavani Ghat</b>							
	Medical and all other depts	1X3				3.00		
	<b>Punnami Ghat</b>							
	Medical and all other depts	1X4				4.00		
	<b>TTD Site</b>							
	Medical and all other depts	1X2				2.00		
	Kummaripalem Medical Camp	1X2				2.00		
	sithara centre for police out post	1X1				1.00		
	at C.V.R. fly over medical camp	1X2				2.00		
						<b>157.00</b>	<b>Nos</b>	
							<b>41.00</b>	

S.No	Description of work	No	Measurements			Contents	Rate	Per
			L	B	D			
							Each	
	<b>Stage Benches of 2'-6"x6'-0"</b>							
	Mahamandapam Kalaradhana	2X1				2.00		
	Kanaka Durga nagar Prasadam Stock point	1X35				35.00		
	Kalaradhana	1X50				50.00		
	at under passage area for clock room	1x22				22.00		
	at under passage area for water packets distribution point	1X29				29.00		
	at kk sala for department staff	1X8				8.00		
	at tollgate	1X4				4.00		
						<b>150.00</b>	<b>Nos</b>	
							<b>176.00</b>	
							Each	
	<b>Water proof shamiyanas with bamboos</b>							
	Mahamandapam Kalaradhana green room	1X2		5.49	2.74	30.08		
	Ambulance	1X1		7.32	5.49	40.19		
	Police out post	1X1		7.32	3.66	26.79		
	Police out post	1X1		9.14	4.57	41.77		
	Kanaka Durga nagar from stone Mandapam annadanam over Q lines	1X3		7.32	3.66	80.37		
		1X4		5.49	2.74	60.17		
	Pannel board	1X1		5.49	2.74	15.04		
	water packects	1X1		5.49	2.74	15.04		
	Kanaka Durga nagar Laddu Stock point	1X2		7.32	3.66	53.53		
	Medical and forest dept	1X2		9.14	4.57	83.54		
	Ashoka Pillaer	1X1		7.32	3.66	26.79		
	Triloka counters	1X2		5.49	2.74	30.09		
	Vinayaka Temple medical and water packects	1X1		6.10	3.05	18.60		
	for handicapped at sithamma vari padalu ghat	1X1	5.49	2.74		15.04		
	for clock room at sithamma vari padalu ghat	1X1	5.49	2.74		15.04		
	<b>kesa kandana sala area</b>							
	for barbers dining section	1X1	5.49	2.74		15.04		
	for pilgrims at kk sala	1X1	10.98	10.98		120.56		
		1X1	5.49	2.74		15.04		
		1X1	10.98	3.66		40.19		
	Durga Ghat							
		1X2	5.49	2.74		30.09		
	TTD Site	1X1	7.32	3.66		26.79		
	Punammi ghat	1X1	10.97	5.49		60.23		
		1X2	5.49	2.74		30.09		
	Bhavani Ghat	1X1	5.49	2.74		15.04		
		1X2	7.32	3.66		53.58		
	sittara centre for police out post	1X3	5.49	2.74		45.13		

S.No	Description of work	No	Measurements			Contents	Rate	Per
			L	B	D			
		1X1	7.32	3.66		26.79		
	chittinagar for plice out post	1X1	5.49	2.74		15.04		
						<b>1,045.69</b>	<b>sqm</b>	
							<b>96.00</b>	
							1 sqm	
	<b>Providing geeenmat (2'-6"width)</b>							
	vinayaka temple to Boddu bomma	1x3	326.44			979.32		
	Foot over bridge to tollgate	1X3	213.36			640.08		
	Kanakadurga nagar Q line	4X3	12.19			146.28		
	Kanakadurga nagar Q line	20X1	18.29			365.80		
	from stone mandapam to annadanam Q lines	1X3	29.26			87.78		
		1X1	13.41			13.41		
		1X1	32.00			32.00		
	vinayaka temple to divider ending in Q-lines	1x3	326.10			978.30		
	from ending of ladder to tollgate in Q-lines	1X3	181.70			545.10		
						<b>3,788.07</b>	<b>Rmt</b>	
	<b>Providing geeenmat (5"-0"width)</b>						<b>1Rmt</b>	
	Sivalayam steps to arjun street	1X2	106.68			213.36		
	Hamsavahanam	1X1	636.00			636.00		
	Road to kalaradhana	1X2	22.25			44.50		
		1X2	18.28			36.56		
	Kalaradhana inside	1X12	31.09			373.08		
	East side	1X2	22.86			45.72		
	steps	1X2	9.45			18.90		
	Stage	1X3	3.66			10.98		
	Keshakandana sala Media to annadanam	1X2	10.97			21.94		
	Fire dept	1X2	7.32			14.64		
	Police out post	1X3	9.14			27.42		
	Kalaradhana Road up to arjun street front of prasadam counters	1X2	243.84			487.68		
	Prasadam counters exit Q lines	1X4	12.19			48.76		
		1X5	18.29			91.45		
		1X1	23.77			23.77		
	Back side	1X2	6.86			13.72		
		1X2	13.10			26.20		
	Prasdam stock point	1X2	6.10			12.20		
		1X4	3.66			14.64		
		1X4	5.18			20.72		
		2X2	3.05			12.20		
		1X1	9.14			9.14		
	Sarees sales counter	1X4	16.45			65.80		
	Medical and other depts	2X4	10.97			87.76		
	Tollgate out post	1X1	2.40			2.40		
	Divider ending to sudhakar hotel(In Q-line 1)	1X6	58.00			348.00		

S.No	Description of work	No	Measurements			Contents	Rate	Per
			L	B	D			
		1X3	36.00			216.00		
		1X2	154.00			308.00		
		1X3	13.60			40.80		
	<b>padmavathi ghat</b>							
	Medical and other depts	1X3	8.80			26.40		
	Tollgate out post	1X1	2.40			2.40		
	<b>Bhavani Ghat</b>							
	Medical and all other depts	1X2	5.49			10.98		
	<b>Punnami Ghat</b>							
	Medical and all other depts	1X4	10.97			43.88		
	<b>TTD Site</b>							
	Medical and all other depts	1X2	7.32			14.64		
	<b>kesakandana sala</b>							
	Medical and all other depts	1X4	10.97			43.88		
	current room	1X2	5.49			10.98		
	department staff room	1X2	5.49			10.98		
	inside kk sala for pilgrims	1X7	10.97			76.79		
	Mat for compartments	1X10	42.50			425.00		
		1X9	42.50			382.50		
		1X9	42.50			382.50		
	vinayaka swamy temple							
	officers point	1X2	5.49			10.98		
	at JMGD intake well near head water works	1X2	36.90			73.80		
	at kummaripalem junction	1X2	44.00			88.00		
	Tollgate to Kummaripalem <b>Pg No:14 MB.No.346</b>	1X1	121.92			121.92		
	On road	1X1	91.41			91.41		
	On road	1X1	167.00			167.00		
	On road	1X1	167.11			167.11		
	On road	1X1	67.67			67.67		
	On road	1X1	67.06			67.06		
	On road	1X1	13.11			13.11		
	On road	1X2	17.07			34.14		
	On road	1X1	37.80			37.80		
	On road	1X2	37.25			75.50		
	On road	1X1	47.21			47.21		
	On road	1X2	15.24			30.48		
	On road	1X1	83.82			8.82		
	On road	1X1	135.03			135.03		
						<b>5,940.31</b>	<b>rmt</b>	<b>27.00</b>
								1 rmt
	<b>Providing Plastic Tarpaulin</b>							
	Annadanam	1x1	10.97	5.49		60.23		
	Keshakandanasala	1x1	50.00	25.00		1,250.00		
	Sarees counter	1x1	20.00	15.00		300.00		
						<b>1,610.23</b>	<b>Sqm</b>	<b>12.00</b>
								1 Sqm
	<b>Providing PVC Drums</b>							
	Keshakandana sala	1x34				34.00		

S.No	Description of work	No	Measurements			Contents	Rate	Per
			L	B	D			
	add 10% area variations					3.40		
						<b>37.40</b>	<b>Nos</b>	<b>105.00</b>
								Each
	<b>White cloth</b>							
	Hire charges for supplying, laying and removing of White cloth The rate is for festival period maintained by the department..							
	Kanaka Durga Nagar	1X5	1.83	1.83		16.74		
	Sarees sales counter	1X5	1.83	1.83		16.74		
	Photo stall sound system	1X5	1.83	1.83		16.74		
	Sarees sales counter side	1X5	5.49	5.49		150.70		
	Tollgate	1X2	1.83	1.83		6.70		
	<b>Padmavathi Ghat</b>							
	Medical and all other depts	1X5	1.83	1.45		13.27		
	<b>seethamavari padalu ghat officers point</b>	1X6	1.83	1.45		15.92		
	<b>kesakandana sala officers point</b>	1X6	1.83	1.45		15.92		
	for officers point at kesakandana sala	1X1	22.87	2.74		62.66		
	Inside kk sala	1X4	1.83	1.45		10.61		
	Durga ghat							
	Medical and all other depts	1X4	1.83	1.45		10.61		
	<b>Bhavani Ghat</b>							
	Medical and all other depts	1X2	1.83	1.45		5.31		
	<b>Punnami Ghat</b>							
	Medical and all other depts	1X6	1.83	1.45		15.92		
		1X1	5.49	3.05		16.74		
	<b>TTD Site</b>							
	Medical and all other depts	1X4	1.83	1.45		10.61		
	Kummaripalem Medical Camp	1X2	1.83	1.45		5.31		
	at C.V.R. fly over medical camp	1X2	1.83	1.45		5.31		
						<b>395.82</b>	<b>Sqm</b>	<b>18.00</b>
								<b>1 Sqm</b>
6	Hire charges for supplying, laying and removal of canvas tarpaulin. The rate includes watch and ward against theft and fire accidents to and fro transportation charges and all labour, incidental charges etc., complete. The tarpaulin should be in a good condition through out the festival and should be removed after the same is over.The rate is for festival period as decided by the devasthanam.							
	Kanaka Durga Nagar	1X4	7.32	5.49		160.76		
	Sarees Counter	1X2	7.32	5.49		80.38		
	Kesa Kandana sala inside	1X1	48.77	24.38		1189.01		
	at uder passege for water packets ponit	1X1	5.49	7.32		40.19		
	for department staff	1X2	5.49	2.74		30.09		
						<b>1,500.42</b>	<b>Sqm</b>	<b>90.00</b>
								<b>1 Sqm</b>

S.No	Description of work	No	Measurements			Contents	Rate	Per
			L	B	D			
7	Hire charges for supplying, laying and removing of shamiyanas with Bamboo posts or casuriana posts with necessary frame-work , tables, chairs and other materials etc., The rate includes watch and ward against theft and fire accidents, to and fro transportation charges and all labour, incidental charges etc., complete. The shamiyanas should be in a good condition throughout the festival and should be removed after the same is over.The contractor should be supplying the materials whenever necessary during the festival period. The rate for each item is for festival period as decided by the devasthanam including maintenance during the said period including laying, removing, loading, unloading, transport charges.							
	<b>Providing shamiyanas with Bamboos 24'-0"x 12'-0"</b>	1X2				<b>2.00</b>	<b>Nos</b>	<b>1,070.00</b>
								<b>Each</b>
	<b>Providing shamiyanas with Bamboos 18'-0"x 9'-0"</b>	1X3				<b>3.00</b>	<b>Nos</b>	<b>690.00</b>
								<b>Each</b>
8	Hire charges for erection and removal of Flat roof or sloped roof MS pipes frame work, White/colour ceiling cloth with frills for decorating the shed and Plain border around complete.The rate includes watch and ward against theft and fire accidents, to and fro transportation charges and all labour chages etc, complete and should be in a good condition throughout the festival and should be removed after the same is over.if the including maintainance during the said period. The rate is for festival period as decided by the devasthanam for festival days							
	Durga Ghat	1X1	6.00	5.00		<b>30.00</b>	<b>Sqm</b>	<b>60.00</b>
								<b>1 Sqm</b>
								<b>Total</b>
								Add GST @ 12%
								Add Labour cess @1%
								Unforceen Item
								<b>Grand Total</b>

**Assistant Engineer**  
**SDMSD**  
**Vijayawada**

**Dy. Executive Engineer**  
**SDMSD**  
**Vijayawada**

**Executive Engineer**  
**SDMSD**  
**Vijayawada**

**Executive Office:**  
**SDMSD**  
**Vijayawada**



















<b>Amount</b>
<b>2,140.00</b>
<b>2,070.00</b>
<b>1,800.00</b>
<b>28,69,496.00</b>
<b>3,44,340.00</b>
<b>28,695.00</b>
<b>7,469.00</b>
<b>32,50,000.00</b>

**r**